



NOTES:

1. PIPING SHALL BE INSTALLED UP TO 2" CURB STOP W/VALVE BOX AND COVER AT TIME OF MAIN INSTALLATION.
2. AUTOMATIC FLUSHING UNIT SHALL BE INSTALLED AFTER MAIN LINE HAS BEEN BACTERIOLOGICALLY TESTED, BUT PRIOR TO TIE-IN.
3. ALL THREADED HARD PIPING SHALL BE BRASS.
4. AT TIME OF ACCEPTANCE WATER DEPARTMENT WILL INSTALL 2" METER.
5. AUTOMATIC FLUSHING UNIT SHALL BE HYDROGUARD HG-1 STANDARD UNIT OR APPROVED EQUAL.

AUTOMATIC WATERMAIN FLUSHING DETAIL

DSGN.	
DRW.	MES
CK.	ML



CONSTRUCTION STANDARDS AND DETAILS

DATE APPROVED	AUGUST 2016
DRAWING NUMBER	WS 15